

CASE STUDY

PROJECT

CLIENT

➤ PEACHY CONSTRUCTIONS

LOCATION

➤ ORMEAU, QLD

PROJECT

➤ WASHDOWN WATER
RECYCLING UPGRADE

OVERVIEW

In 2005 Clearmake designed, manufactured and commissioned a 3000L/h Wash Down Recycling System. After more than 5 years of successful operation, it was time for a system overhaul. To coincide with the overhaul Peachy decided to upgrade the system to incorporate the latest Clearmake design and technology. This upgrade ensured optimum treated water quality and minimised operational costs.



BENEFITS

- Upgraded system operating at current best practice efficiency
- Continued recycling of the wash down water eliminating the use of potable town water
- Elimination of sewer discharge from wash down operations

MORE INFORMATION

Please visit
www.clearmake.com.au
or call 1800 700 267

SOLUTION

Clearmake worked with Peachy to review the operation and performance of the existing system and developed an upgrade program to maximise system performance while minimising capital and operational expenditure. The solution included:

- Updated chemical dosing pumps
- Updated chemical dosing regime
- Updated clarifier design
- Updated control system including new use interface
- New media filter

21 Project Ave
Noosaville Q 4566

P 07 5455 6822
F 07 5455 6833

E info@clearmake.com.au
www.clearmake.com.au